

MECHANICAL SERVICES

VICTORIAN PROJECTS
(03) 9798 7780
admin@victorianprojects.com.au
www.victorianprojects.com.au

Project Manager:
Lachlan French
Quotation Prepared For:
Guru Kahlon, Kahlon Building Co
Project Reference:
PVP-1126-D



1. COVER PAGE

Project: 459 Little Collins Street, P2 and P3 offices variation (hot and cold takeoffs with room control)
Project Address: 459 Little Collins Street, Melbourne VIC 3000 (Levels 3, 4, 8, 9, 10 and 14)
Builder: Kahlon Building Co (UnitedCo), attention Guru Kahlon
Proposal Reference: PVP-1126-D
Revision: 0
Date: 10 November 2026

Prepared by:
Name: Jen Porras
Title: Senior Estimator
Phone: (03) 9798 7780
Email: jen@victorianprojects.com.au

10 Year Workmanship Warranty
Conditions apply. See Warranty section for details.

2. EXECUTIVE SUMMARY

Project Overview

We understand the project involves:

- A variation to the flex rough-in works: new hot and cold takeoffs with a room controller for 15 offices off mixing boxes P2 and P3, on Levels 3, 4, 8, 9, 10 and 14.
- The existing P2 and P3 boxes have 160 mm inlets that cannot carry the air the new offices need, and the inlet is built into the box so it cannot be made bigger. One or two offices come off each box and are fed from new takeoffs on the existing hot and cold primary ducts.
- Each office gets its own room controller, so it keeps its heating and cooling. Each of the six floors gets one new 240 V circuit and a 24 V supply.

This proposal outlines the supply, installation, testing and completion of the mechanical services in accordance with:

- Drawings: Flex Rough In Set Out, L3, L4, L8, L9, L10 and L14, Rev G
- Specifications: none issued
- Revision: Rev G

We are committed to delivering structured project management, coordinated installation, and compliant mechanical systems aligned with the overall construction program.

3. PROJECT UNDERSTANDING

The works involve:

- Taking 15 offices off mixing boxes P2 and P3 and feeding each from a new cold takeoff and a new hot takeoff above the office.
- A motorised round damper on each takeoff and one Smart Temp SMT-850 Halo room controller per office, running standalone.
- One new 240 V circuit and 24 V supply on each floor, by our licensed electrical subcontractor.

Key project considerations include:

- Staging requirements: work is done before plaster while the ceiling is open, with the office count confirmed at rough in, before sheeting.
- Access constraints: ceiling left open, or access left, at each office until our work is in.
- Live environment considerations: normal working hours, no after hours work.
- Critical coordination items with other trades: our electrical subcontractor for the 24 V cabling and floor circuits, and the builder for ceiling sequence around L3.15, L3.21 and L3.23.

We understand the importance of maintaining program certainty and minimising disruption to the overall build sequence.

4. SCOPE OF WORKS

4.1 Hot & Cold Takeoffs and Dampers (per office)

Inclusions:

- Supply and cut in a new takeoff on the existing cold primary duct and a new takeoff on the existing hot primary duct above the office.
- Fit a round motorised damper on each takeoff, being a Smart Temp P-Barrel-10 (250 mm) or P-Barrel-8 (200 mm) metal body with a Belimo LM24A-SR actuator.
- Join both takeoffs into the office's existing supply flex, and disconnect that flex from the existing mixing box.
- Insulate the new takeoffs and damper bodies, and make good the existing duct insulation at each cut in.

Deliverable Outcome: Hot and cold takeoffs and motorised dampers installed to each of the 15 offices, with the office flex moved off the existing mixing box.

4.2 Room Control (per office)

Inclusions:

- Supply and install one Smart Temp SMT-850 Halo room controller in each office. It runs the hot damper for heating and the cold damper for cooling, and holds the cold damper at a minimum position so the office always gets air.
- 24 V control cabling from the floor power supply to the controller and both actuators
- Set up, commission and balance each office.

Deliverable Outcome: Each office running standalone on its own controller.

4.3 Electrical (per floor)

Inclusions:

- New 240 V circuit off the nearest board on that floor to a power point in the ceiling, with MCB and isolator, for one Smart Temp SZ-PS 24 V AC power supply (2 A plug pack) serving the offices on that floor
- Test, tag and electrical certificate of compliance.

Deliverable Outcome: Six floors, each with a tested 24 V supply and a certificate of compliance.

4.4 Offices Covered

Inclusions:

- The count is off our Rev G drawings and is confirmed at rough in, before sheeting.
- Level 3: L3.15 off P2, L3.21 and L3.23 off P3 (3 offices)
- Level 4: L4.18 off P2, L4.22 and L4.23 off P3 (3 offices)

- Level 8: one UN1 slot off P2, L8.18 and L8.19 off P3 (3 offices)
- Level 9: one L9.13 slot off P2 (S17 moves to C3, no charge), L9.17 off P3 (2 offices)
- Level 10: L10.18 off P2, L10.24 off P3 (2 offices)
- Level 14: L14.18 off P2, L14.23 off P3 (2 offices)
- Total: 15 offices.

5. INCLUSIONS

This proposal includes:

- Labour
- Materials
- Plant & equipment
- Site supervision
- Electrical works by our licensed electrical subcontractor for the 24 V cabling and the floor circuits
- Commissioning and balancing of each office
- Certificates of compliance
- SWMS documentation
- 12-month defects liability period

6. EXCLUSIONS

This proposal excludes the following unless specifically noted:

- Builders works including cutting, patching, painting and making good
- Connection to, integration with or programming of the BMS
- Any work on the existing P2 and P3 mixing boxes other than disconnecting the moved office flex
- Work once the ceiling is closed, including access, patching and making good
- Electrical works other than the 24 V control cabling and floor circuits in section 4
- Temporary power, water and amenities
- Waste bins and site clean beyond our own rubbish
- Asbestos and hazardous materials
- After hours work
- EBA labour rates. The price is on our standard non-EBA rates, and if the site requires EBA rates the change is a variation
- Removing this work if the Stage 2 box replacement goes ahead later
- Program acceleration
- Retention and bank guarantees
- Liquidated damages
- Warranty on existing equipment
- Any works not specifically detailed in this proposal

7. BUILDER RESPONSIBILITIES / BY OTHERS

The following are to be provided by others:

- Ceiling left open, or access left, at each office until our work is in, including around L3.15, L3.21 and L3.23
- Access at rough in to confirm the offices off P2 and P3 on each floor before sheeting
- Site access and lay down area
- Temporary power and lighting
- Waste bins
- Protection of our completed works

- Nominated program
- Access panels in the ceiling at each motorised damper, for service
- Controller position in each office nominated before sheeting, so the cable can be dropped in the wall

8. PROJECT DELIVERY METHODOLOGY

8.1 Project Management

Assigned Project Manager: Lachlan French
Site Supervisor: Daniel Rogers

We will provide:

- Pre-start coordination meeting
- Procurement scheduling
- Ongoing coordination with builder and trades
- Progressive inspections
- Completion handover documentation

8.2 Safety & Compliance

- SWMS provided prior to mobilisation
- Licensed mechanical contractor
- Public Liability Insurance
- Works compliant with relevant Australian Standards
- Trained and qualified trades personnel

8.3 Quality Assurance

- Test, tag and certificate of compliance on each floor circuit
- Installation inspections

9. PROGRAM & TIMEFRAME

Estimated commencement: TBC, on written approval and while the ceiling is open at each level
Estimated duration: TBC

Subject to:

- Award date
- Site access
- Material lead times
- Builder program alignment

Pricing is based on continuous, uninterrupted access to the site during normal working hours. Any standby time or delay caused by others will be charged at our day works rates.

Critical procurement items:

- Belimo LM24A-SR actuators (Lead time: ETA mid November, to be confirmed on order)
- Smart Temp SMT-850 controllers, P-Barrel damper bodies and SZ-PS power supplies (in stock)

10. COMMERCIAL SUMMARY

Level 3 (3 offices)	$12,897.00
Level 4 (3 offices)	$12,897.00
Level 8 (3 offices)	$12,897.00
Level 9 (2 offices)	$9,145.00
Level 10 (2 offices)	$9,145.00
Level 14 (2 offices)	$9,145.00
Total Lump Sum (Excl. GST)	$66,126.00
GST (10%)	$6,612.60
Total Contract Sum (Incl. GST)	**$72,738.60**

- Rates: $3,752.00 per office and $1,641.00 per floor, ex GST. Each level is the number of offices x $3,752.00 plus $1,641.00.
- We confirm the offices off P2 and P3 on each floor at rough in, before sheeting. The per office and per floor rates apply to the confirmed count.
- Priced on doing the work before plaster while the ceiling is open, in normal working hours.
- P1, P5, P6 and P7 are balanced as they are, at no charge.
- Written approval of this price and time is needed before we install, as set out in clause 3.4 of the contract.
- All variations will be submitted in writing for approval prior to proceeding.
- This proposal is valid for 30 days from the date of issue.
- Payment terms: progress claims monthly, payment 30 days from end of month.
- Retention is excluded from this proposal.
- Equipment pricing is subject to supplier price increases if this proposal is not accepted within the validity period.

11. AFTER-HOURS WORKS

After-hours works can be provided at the following rates:

- Weekday after-hours: $155.00 per hour per technician

Subject to prior approval and coordination with the builder.

12. CAPABILITY STATEMENT

Victorian Projects is a mechanical services contractor delivering commercial HVAC, ventilation, pipework, and specialist mechanical systems across Melbourne. With over 50 years of combined industry experience, we support Tier 3 builders with structured project management, in-house sheet metal fabrication, switchboard manufacturing, and coordinated delivery with our electrical subcontractor.

Our team has delivered projects across government, education, emergency services, commercial offices, industrial facilities, and public infrastructure environments. We understand the importance of program certainty, trade coordination, safety compliance, and proactive communication. Our approach focuses on

early coordination, clear scope definition, controlled procurement, and disciplined site supervision to minimise variations and support on-time project completion.

We operate as a delivery-focused subcontractor, responsive, solution-oriented, and aligned with the builder's program objectives.

13. WARRANTY

Workmanship warranty

Victorian Projects warrants the workmanship of this installation for twelve (12) months from the date of practical completion of our works.

Where the system is maintained by Victorian Projects under a current maintenance agreement, this workmanship warranty extends to ten (10) years from the date of practical completion of our works. The extended warranty applies only during periods in which the maintenance agreement is current. It does not continue during any lapse in the agreement and does not revive if the agreement is later reinstated. The twelve (12) month base warranty is unaffected.

The extended warranty applies only where the maintenance agreement provides the manufacturer’s recommended service frequency for the plant installed. Where the agreement provides less than that frequency, the twelve (12) month base warranty applies.

The extended warranty is not transferable to a new owner or tenant unless the maintenance agreement transfers with it and Victorian Projects provides written confirmation.

Our liability under this warranty is limited to the value of the original contract sum, to the extent permitted by law.

Equipment warranty

All plant and equipment supplied under this proposal is covered by the manufacturer’s warranty. For this project that is the Belimo actuators and the Smart Temp controllers, damper bodies and power supplies, for the period set by each manufacturer, commencing at installation. Warranty registration and commissioning documentation will be lodged with the manufacturer on completion.

What this warranty covers

Installation workmanship only, being the quality and compliance of the installation carried out by Victorian Projects.

What this warranty does not cover

- Materials, equipment and products supplied as part of the works, which are covered by their respective manufacturers’ warranties.
- Fair wear and tear.
- Damage, misuse, unauthorised alteration, or works carried out by others.
- Consumable and limited life items including filters, flexible ductwork, flexible connections and condensate drain lines.
- Any failure arising from the system not being maintained in accordance with the manufacturer’s recommended schedule.
- Faults arising from base building services, power supply, or conditions outside our control.

Contact us to continue maintenance as an ongoing agreement once the defects liability period ends.

14. TERMS & CONDITIONS

This proposal is subject to the Victorian Projects Standard Terms and Conditions (Version 03, 30 September 2026), attached as Appendix A.

In the event of award, works will be carried out under:

- This proposal and Appendix A. Where Victorian Projects has signed a subcontract or agreed in writing to builder head contract requirements, those terms apply to the extent they expressly vary this proposal.

15. ACCEPTANCE

To proceed, please issue a purchase order referencing the proposal details below or sign acceptance.

Proposal Reference: PVP-1126-D
Project: 459 Little Collins Street, P2 and P3 offices variation

Please tick the option being accepted:
☐ Level 3 only, $12,897.00 ex GST
☐ Selected levels only, at the level prices in section 10. Levels: _____
☐ Full proposal as detailed above, $66,126.00 ex GST

Accepted By:

Name: _____

Company: _____

Position: _____

Signature: _____

Date: _____

APPENDIX A, VERSION 03, 30 SEPTEMBER 2026

Standard Terms and Conditions

Standard Terms and Conditions for Victorian Sheet Metal Pty Ltd ABN 15 624 335 262 trading as Victorian Projects ("Victorian Projects"). Version 03, 30 September 2026.

These conditions govern every contract for the sale of Goods and/or the provision of services by Victorian Projects to the Customer, constitute all the Terms and Conditions agreed between them to the exclusion of all other Terms and Conditions.

No modification of these Conditions, whether put forward in the Customer's purchase order or otherwise, shall bind Victorian Projects unless agreed to in writing by its authorized employee.

These Conditions supersede any Terms and Conditions which have previously governed contracts for the sale of Goods and Services by Victorian Projects to the Customer.

1. Payment

1.1 AUTHORITY TO PROCEED (ATP Form): Payment terms are as stated in the proposal. Where not stated, payment is due net 30 days from date of invoice. Where the Domestic Building Contracts Act 1995 applies, deposits and progress payments are limited to the amounts permitted under that Act.

a) Payment terms of COD (Cash on Delivery) apply unless payment terms are offered by Victorian Projects. Payment terms will only apply to customers providing the ATP Form filled out and correctly completed. Information will be used solely by Victorian Projects and card information will not be misused or have payments taken out without the client's authority unless the invoice has not been paid on completion or by due date.

b) For the supply and installation of air conditioning units, payment is strictly COD unless otherwise agreed to a maximum of net 30 (thirty) days from the date of invoice.

c) For the provision of service, payment is strictly COD unless otherwise agreed to in writing to a maximum of net 30 (thirty) days from the date of invoice.

d) Payment methods accepted: MasterCard, Visa, Debit, Cash or Bank Transfer. For card payments, a surcharge of 0.5 to 1.5% applies depending on card type.

1.2 The Building and Construction Industry Security of Payment Act 2002 (Victoria) provides for rapid determination of progress claims under building contracts. Adjudication is binding on the Parties and can be recovered as a debt in a Court.

1.3 Payments are to be made to Victorian Projects without any deduction or discount other than as stated in these Terms or in the relevant invoice.

1.4 The remaining balance of the invoice must be paid in full upon Completion unless otherwise stated in the agreement.

1.5 Failure to pay within agreed credit terms will automatically create stop credit until all outstanding amounts are paid.

1.6 Without prejudice to any other remedy, Victorian Projects reserves the right to charge a default charge on overdue payments at an annual rate equal to the Commonwealth Bank's current overdraft rate.

2. Quotations and Prices

Any quotation given by Victorian Projects is a mere invitation to treat and does not constitute a contractual offer. All quotations hold for 30 (thirty) days after issue. Victorian Projects may withdraw or amend a quotation at any time prior to acceptance.

Prices are based on the specification, drawings and/or requests by the Customer. Should the specification or Customer's request change, Victorian Projects reserves the right to vary the quotation price and resubmit for approval.

If electrical connection is not supplied by Victorian Projects, the site electrician must make final connection once installation is complete.

All quoted prices are exclusive of GST unless otherwise stated.

3. Delivery

The times quoted for delivery are estimates only and Victorian Projects accepts no liability for failure or delay in delivery of the Goods. The Customer is not relieved of any obligation to accept or pay for Goods by reason of any delay in delivery. Risk in the Goods passes on delivery to the Customer.

4. Warranty and Claims

Service under warranty is available between 7.30am and 4.00pm Monday to Friday, excluding public holidays. Warranty does not include routine maintenance, filter cleaning, faults from power failure, misuse, lack of maintenance, or operator error.

a) Installation warranty: guarantee of workmanship on new installations for 12 (twelve) months. Where the system is maintained by Victorian Projects under a current maintenance agreement, this extends to 10 (ten) years. See Warranty section of this proposal for full conditions.

b) Service warranty: guarantee of workmanship for service repair work for 3 (three) months.

The Goods come with guarantees that cannot be excluded under the Australian Consumer Law. The Customer is entitled to a replacement or refund for a "major failure" and compensation for other reasonably foreseeable loss or damage.

Warranty claims: contact (03) 9798 7780 or admin@victorianprojects.com.au.

5. Retention of Title

All equipment supplied and installed by Victorian Projects remains the property of the Company until all monies outstanding have been paid.

In the event of default, Victorian Projects or its agents may, on reasonable notice and in accordance with applicable law, enter the Customer's premises to recover the Goods and may recover and resell the Goods.

6. Personal Properties and Securities Act 2009 (PPSA)

These Terms and Conditions constitute a Security Agreement and give rise to a Purchase Money Security Interest (PMSI) in favour of Victorian Projects over Goods supplied to the Customer.

Victorian Projects is entitled to register its interest on the PPSA Register as Collateral. The Customer waives its right to receive notification of any Verification Statement confirming such registration.

The Customer agrees to indemnify Victorian Projects for all costs associated with the registration, amendment or discharge of any Financing Statement and the enforcement of any Security Interest.

7. Retention Money

Unless otherwise provided in writing, the purchaser shall not be entitled to retain any part of the purchase price by way of retention monies to guarantee satisfactory operation of the equipment supplied and installed.

8. Warranties

a) Victorian Projects liability in respect of a breach of a consumer guarantee for Goods not ordinarily acquired for personal/domestic use is limited to: replacement or supply of equivalent products; repair of the products; or payment of the cost of replacement or repair.

b) Other than the express warranties set out in the Warranty section of this proposal, all other warranties whether implied or otherwise are excluded to the extent permitted by law. Victorian Projects is not liable for increased costs, loss of profit/revenue/business, third-party claims, or any special, indirect or consequential loss.

c) Claims for short delivery of Goods must be lodged in writing within 7 (seven) days of the delivery date.

9. Indemnity

To the full extent permitted by law, the Customer will indemnify Victorian Projects from and against any liability and any loss or damage arising directly or indirectly from any breach of these Terms and Conditions by the Customer or its representatives, to the extent that the liability, loss or damage was caused or contributed to by the Customer or its representatives.

10. Exclusions

The price agreed does not include any expense covering damage arising from hidden or unknown contingencies found at the job site, including faults or deterioration of the building structure, pre-existing conditions, heritage orders, or hazardous substances, unless specifically noted in the tender price.

This tender excludes: performing building work (cutting holes, patching, painting, flashing, boxing in); furring in, plinths or platforms; metered electrical mains brought to a point adjacent to equipment; alterations to the switchboard; condensate drains brought to a point adjacent to equipment.

11. General

a) These Terms and Conditions are to be construed in accordance with the laws of the State of Victoria and the Commonwealth of Australia.

b) These Terms and Conditions may only be varied by agreement in writing between the parties.

c) Any conditions found to be void, unenforceable or illegal may, to that extent, be severed.

d) No waiver of any of these Terms and Conditions or failure to exercise a right or remedy shall constitute a further waiver.

If there is any inconsistency between the body of this proposal and these Standard Terms and Conditions, the body of the proposal prevails.

12. Buildability

Constructability is a project management technique to identify obstacles before a project is built to reduce errors, delays, and cost overruns.

Unanticipated circumstances that affect the final price and/or completion time may incur an additional charge. Victorian Projects is not required to identify all buildability issues without a full engineering report, which if required is to be supplied prior to quotation.

13. Cancellation

If the Customer cancels after acceptance, the Customer must pay for all work performed to the date of cancellation, all equipment and materials ordered or delivered that cannot be returned, any supplier restocking or cancellation charges, and reasonable costs incurred in demobilising from site.